

# S 36 SX

Truck-Mounted concrete pump  
with RZ4 placing boom



# SPECIFICATIONS

## Pump Kit on S 36 SX

## 2025-5 120/80 MPS

	U.S.	Metric
Theor. Concrete Output Per Hour (cubic yards - cubic meters)	178	136
Maximum Pressure on Concrete (psi - bar)	1233	85
Maximum Strokes Per Minute	23	23
Pump Cylinder Diameter (in. - mm)	10	250
Pump Cylinder Stroke Length (in. - mm)	79	2000
Differential Cylinder Size (in. - mm)	4.7	120
Maximum Aggregate Size (in. - mm)	2.5	63.5

## Boom Specifications

	U.S.	Metric
Pipeline Diameter (in. - mm)	5	125
Vertical Reach (ft.-in. - m)	118-5	36.1
Horizontal Reach (ft. - m)	104	31.7
Net Horizontal Reach (ft. - m)	96	29.3
Unfolding Height (ft.-in. - m)	28-10	8.8
Section Lengths		
First Section (ft.-in. - m)	26-1	7.95
Second Section (ft.-in. - m)	24-11	7.6
Third Section (ft.-in. - m)	24-11	7.6
Fourth Section (ft.-in. - m)	28-1	8.6
Slewing Range (degrees)	740°	740°
End hose length (ft. - m)	12	3.7

Specifications are subject to change without prior notice.

# RZ4

